

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-21133-00-01  
Spot: W2W2W2SE Sec/Twnshp/Rge: 14-24S-31W  
1349 feet from S Section Line, 2618 feet from E Section Line  
Lease Name: HARMS Well #: 1  
County: FINNEY Total Vertical Depth: 2742 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2766	0	WITH 625 SX CMT
SURF	8.625	558		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2014 12:30 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2014 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 6 BBL GEL WITH 200# HULLS DOWN 4 1/2" CASING. PUMP 4 BBL GEL SPACER DOWN 4 1/2" CASING. PUMP 20 SX CMT PLUG DOWN 4 1/2" CASING. PUMP 5 BBL SPACER. TAG FLUID LEVEL AT 1337'. FILL TO 1000'. PUMP 80 SX CMT FROM 1000' TO 0'. PRESSURED TO 300#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2712	2722		

Received  
KANSAS CORPORATION COMMISSION  
DEC 03 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMEBNT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed *Ken Jehlik* (TECHNICIAN)

12/4/14

RECEIVED

NOV 19 2014

KCC DODGE CITY

KMS