

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24154-00-00
Spot: NENE Sec/Twnshp/Rge: 10-32S-15W
630 feet from N Section Line, 498 feet from E Section Line
Lease Name: DORIS ANN ALEXANDER Well #: 1
County: BARBER Total Vertical Depth: 5200 feet

Operator License No.: 33936
Op Name: GRIFFIN, CHARLES N.
Address: PO BOX 347
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4640		WITH 2 SX CMT
CIBP	5.5	4900		
CIBP	5.5	4980		
PROD	5.5	5194	2958	WITH 200 SX CMT
SURF	8.625	262		WITH 190 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/07/2014 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JR GRIFFIN Company: CHARLES N. GRIFFIN Phone: (972) 342-4648

Proposed Plugging Method: SET CIBP @ 4640' & 2 SX CMT. PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2014 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4640' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4988	5002		
4920	4955		
4687	4691		

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

12/4/14 COM

District: 01

RECEIVED
NOV 19 2014
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

ST