

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24210-00-00
Spot: E2NENESE Sec/Twnshp/Rge: 20-17S-22W
2208 feet from S Section Line, 133 feet from E Section Line
Lease Name: IRMA Well #: 1
County: NESS Total Vertical Depth: 4399 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1548		WITH 200 SX CMT
PROD	5.5	4370	0	WITH 350 SX CMT
SURF	8.625	263		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2014 9:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS, THEN GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2014 10:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 50 SX CMT WITH 300# HULLS, 17 SX GEL WATER, & 150 SX CMT. WELL ON VACUUM. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#. WAITED 4 HOURS & TOPPED OFF WITH 40 SX CMT. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4272	4280		

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

12/4/14 CKM

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
NOV 21 2014
KCC DODGE CITY

Form CP-2/3