

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24211-00-00
Spot: NESESW Sec/Twnshp/Rge: 20-17S-22W
967 feet from S Section Line, 2304 feet from W Section Line
Lease Name: WANDELENE Well #: 1
County: NESS Total Vertical Depth: 4349 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| DVT | 5.5 | 1490 | | WITH 200 SX CMT |
| PROD | 5.5 | 4340 | 0 | WITH 350 SX CMT |
| SURF | 8.625 | 262 | | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2014 11:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS THEN GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2014 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 50 SX CMT WITH 300# HULLS, 17 SX GEL WATER & 150 SX CMT. MAXIMUM PRESSURE 2000#. SHUT IN PRESSURE 1600#. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4268 | 4273 | | |

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Michael J. Maier
(TECHNICIAN)

12/4/14 ckm

RECEIVED
NOV 21 2014
KCC DODGE CITY

ST