

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25250-00-00  
Spot: NESESESW Sec/Twnshp/Rge: 20-17S-22W  
345 feet from S Section Line, 2473 feet from W Section Line  
Lease Name: WANDELENE Well #: 2  
County: NESS Total Vertical Depth: 4280 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1517		WITH 200 SX CMT
PROD	5.5	4273	0	WITH 300 SX CMT
SURF	8.625	222		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2014 1:00 PM  
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY  
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PLUG ON BOTTOM WITH 50 SX CMT WITH 300# HULLS THEN GEL SPACER TO 1550'. PUMP CMT TO SURFACE. CHECK 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2014 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT WITH 300# HULLS, 17 SX GEL WATER & 175 SX CMT.  
MAXIMUM PRESSURE 1400#. SHUT IN PRESSURE 1000#. TIED ONTO BACKSIDE &  
PUMPED 15 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4273	4280	OH	

Received  
KANSAS CORPORATION COMMISSION  
DEC 01 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

12/4/14 CEM

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
NOV 21 2014  
KCC DODGE CITY

ST