

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-30113-00-00
Spot: SENWSW Sec/Twnshp/Rge: 7-17S-9W
1938 feet from S Section Line, 4247 feet from E Section Line
Lease Name: MUSENBERG C Well #: 4
County: ELLSWORTH Total Vertical Depth: 3241 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3050		
PROD	5.5	3240		100 SX
SURF	8.625	276		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2014 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM LYMAN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 11/21/2014 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP PREVIOUSLY SET AT 3050', CAPPED WITH 3 SX'S CEMENT. PERFORATE AT 1250', 925', AND 330'. RUN TUBING TO 1250' AND PUMP 35 SX'S WITH 2% CC, PULL TUBING OUT TO 600' AND WAIT 1 HOUR. ATTEMPT TO TAG CEMENT WITH SAND LINE, COULD NOT. RUN TUBING BACK DOWN TO 1250' AND PUMP 35 SX'S CEMENT WITH 3% CC, GOT PARTIAL CEMENT RETURNS, WAITED 10 MINUTES AND PULLED TUBING TO 925' AND PUMPED 35 SX'S, PULL TUBING TO 330' AND CIRCULATED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3240	3241	OH	
2640	2640	CSG	TOP OF CEMENT

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #9324. COPELAND TICKET #42282.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

12/4/14 cpm

JK