

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20244-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 20-21S-34W
650 feet from S Section Line, 641 feet from E Section Line
Lease Name: SMITH Well #: 1
County: FINNEY Total Vertical Depth: 5050 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3006		
PROD	5.5	3300	1141	WITH 300 SX CMT
SURF	8.625	361		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2014 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SQUEEZE PERFS WITH 60 SX CMT & 100# HULLS. PLUG AT 1150' WITH 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 10/28/2014 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PUMP 60 SX CMT WITH 100# HULLS FROM 2300' TO 1718'. TAG TOC IN 5 1/2" AT 1718'. BLOW CASING COLLAR AT 1141' & SQUEEZE IN 50 SX CMT AT 1000# LEAVING CMT HALF IN & HALF OUT OF THE CASING. SHOT CASING OFF AT 631'. PULL TO 390'. PUMP 50 SX CMT AT 390'. PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
3177	3180		
2584	2592		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Kenny Sullivan (TECHNICIAN)

12/4/14

RECEIVED
NOV 11 2014
KCC DODGE CITY

KMS