

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-21216-00-00
Spot: SESE Sec/Twnshp/Rge: 22-29S-41W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: KENDRICK 22 Well #: 3
County: STANTON Total Vertical Depth: 5706 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: ATTN: FRANK DAVIS P.O. BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2353		
PROD	5.5	5641	2738	WITH 310 SX CMT
SURF	8.625	1666		WITH 610 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2014 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: BP @ 2353'. PLUG AT 5410' WITH 30 SX CMT & 100# HULLS. PLUG AT 1700' WITH 80 SX CMT. PLUG AT 560' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 11/11/2014 3:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

RAN TBG, NO BRIDGE PLUG FOUND. TAG OUT AT 5600'. CIRCULATED HOLE WITH 120 BBLs MUD. SQUEEZED PERFS AT 5410' WITH 30 SX CMT & 100# HULLS. PRESSURE TO 500#. HELD. 1ST PLUG AT 1700' WITH 80 SX CMT. 2ND PLUG AT 560' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CIRCULATED CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5436	5438		
5410	5420		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS A CEMENT BU ORR ENTERPRISES.

Plugged through: TBG

12/4/14 OKM

District: 01

Signed Larry A. Harris
(TECHNICIAN)

RECEIVED
NOV 19 2014
KCC DODGE CITY

km 5