

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23489-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 3-21S-12W  
2060 feet from N Section Line, 1280 feet from E Section Line  
Lease Name: RUGAN "B" Well #: 1  
County: STAFFORD Total Vertical Depth: 3457 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3449	1742	WITH 150 SX CMT
SURF	8.625	382		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2014 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3378' & CAP WITH 5 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 11/12/2014 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND BACK TO 3372' WITH 5 SX CMT. 1ST PLUG AT 674' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 422' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3449	3457	OH	

Received  
KANSAS CORPORATION COMMISSION  
DEC 01 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

12/4/14 CAM

RECEIVED  
NOV 19 2014  
KCC DODGE CITY

SP