

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10052-00-00
Spot: SENW Sec/Twnshp/Rge: 8-22S-41W
3294 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HCU Well #: 0821
County: HAMILTON Total Vertical Depth: 2764 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2688		
PROD	4.5	2764	0	WITH 500 SX CMT
SURF	8.625	198		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/13/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2014 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2688'. PUMP 35 SX CMT FROM 2657' TO 2140. RUN BOND LOG FROM 1340' TO 0'. TOC @ 12'. RUN TBG TO 1200' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2738	2756		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

12/4/14 CCM

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
NOV 20 2014
KCC DODGE CITY