

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20086-00-00  
Spot: NWNW Sec/Twnshp/Rge: 36-23S-41W  
4609 feet from S Section Line, 4658 feet from E Section Line  
Lease Name: HCU (PAT 1) Well #: 3631  
County: HAMILTON Total Vertical Depth: 2500 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2382		WITH 35 SX CMT
PROD	4.5	2497	0	JWITH 485 SX CMT
SURF	8.625	348		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2014 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2014 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 2382' WITH 35 SX CMT ON TOP OF CIBP UP TO 1880'. RAN BOND LOG FROM 1000' TO 0'. TOC @ 75'. RUN TBG TO 945' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
DEC 03 2014  
CONSERVATION DIVISION  
WICHITA, KS


Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

12/4/14 cfm

District: 01

Signed



(TECHNICIAN)

RECEIVED

NOV 19 2014

KCC DODGE CITY

Form CP-2/3

KMS