

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20463-00-00
Spot: SW Sec/Twnshp/Rge: 29-22S-40W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HCU Well #: 2920-B
County: HAMILTON Total Vertical Depth: 2774 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2558		
PROD	4.5	2774	0	WITH 690 SX CMT
SURF	8.625	360		WITH 220 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2014 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2558' WITH 35 SX. PULL TBG TO 1250' & CIRCULATE CMT TO SURFACE. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 10/30/2014 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 2558'. SPOT 35 SX CMT FROM 2558' TO 2046' TO COVER ANHYDRITE. PULL TBG TO 1250' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 250 PSI.

Perfs:

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

12/4/14CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV - 6 2014
KCC DODGE CITY

[Signature]