

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21810-00-00  
Spot: W2NESE Sec/Twnshp/Rge: 25-30S-19W  
1980 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HWY "A" Well #: #1-25  
County: KIOWA Total Vertical Depth: 5121 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 9342 E CENTRAL  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>I1</u>	<u>8.625</u>	<u>642</u>		<u>WITH 400 SX CMT</u>
<u>SURF</u>	<u>13.375</u>	<u>252</u>		<u>WITH 350 SX CMT</u>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2014 2:30 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: LANNY SALOGA Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1140' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 11/03/2014 4:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1140' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4 FLO SEAL BY BASIC ENERGY.

Plugged through: DP

12/4/14 CPM

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
NOV 20 2014  
KCC DODGE CITY

SP