

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20734-00-00
Spot: SESENE Sec/Twnshp/Rge: 17-12S-15W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: OFE Well #: 3
County: RUSSELL Total Vertical Depth: 3306 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3305		375 SX
SURF	8.625	724		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2014 9:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: G L M COMPANY Phone: (785) 639-5415

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2014 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

4 1/2" casing parted at 725' - 730'. Could not get back down in casing with fishing tool to get tubing and packer out of hole. Ran tubing open ended. Got inside 4 1/2" casing and stacked out at 2450' (Top of tubing app. 850' and packer left in well.) Pulled tubing to 2430' and pumped 100 sx cement circulating fluids out of the braden head and backside. Pulled tubing to 1400' and pumped 200 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 50 sx cement. Circulated out braden head and shut in w/150 psi.

GPS: 39.00982 -099.00307

Perfs:

Top	Bot	Thru	Comments
3249	3253		
3009	3011		
2989	2992		
2970	2973		
2572	2576		

Remarks: QUALITY CEMENTING TICKET # 726

Plugged through: TBG

12/4/14 CKM

District: 04

Signed Ray A Dinkel

KCC WICHITA

(TECHNICIAN)

CM

NOV 26 2014

RECEIVED