

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25219-00-00  
Spot: SWSESESE Sec/Twnshp/Rge: 15-19S-22W  
329 feet from S Section Line, 456 feet from E Section Line  
Lease Name: KLEWENO Well #: 1-15  
County: NESS Total Vertical Depth: 4362 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1462		CEMENTED WITH 190 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	4.5	4361	0	WITH 125 SX CMT
SURF	8.625	223		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2014 10:30 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY Phone: (785) 623-0533

Proposed Plugging Method: PUMP 60 SX CMT WITH 400# HULLS, SPACER TO 1700', THEN CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2014 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 60 SX CMT WITH 500# HULLS, SPACER TO 1700' & 65 SX CMT. PRESSURED TO 1400#. SHUT IN WITH 1200#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4361	4362		
4252	4254		

Received  
KANSAS CORPORATION COMMISSION  
DEC 01 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

12/4/14 OKM

District: 01

RECEIVED  
NOV 21 2014

Signed Michael Maier  
(TECHNICIAN)

KCC DODGE CITY