

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-22041-00-00
Spot: S2NWSWSE Sec/Twnshp/Rge: 2-16S-19W
720 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GOTTSCHALK A Well #: 1
County: RUSH Total Vertical Depth: 3718 feet

Operator License No.: 33922
Op Name: MUSTANG ENERGY CORPORATION
Address: PO BOX 1121
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3172		WITH 2 SX CMT
CIBP		3420		
PROD	5.5	3713	2169	WITH 140 SX CMT
SURF	8.625	1242		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2014 11:00 AM
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY Phone: (785) 623-0533

Proposed Plugging Method: CIBP @ 3180' WITH 2 SX CMT. PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 11/11/2014 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 3172' WITH 2 SX CMT. 1ST PLUG AT 1278' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 642' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3612	3622		
3303	3393		
3222	3224		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL.

Plugged through: CSG

12/4/14 CRM

District: 01

RECEIVED
NOV 21 2014
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)

KMS
Form CP-2/3