

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24379-00-01
Spot: W2NESWNE Sec/Twnshp/Rge: 30-19S-24W
1650 feet from N Section Line, 1850 feet from E Section Line
Lease Name: MELLIES OWWO Well #: 1C
County: NESS Total Vertical Depth: 4465 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4325		WITH 2 SX CMT
DVT		1621		CIRCULATED TO SURFACE WITH 275 SX CMT
PROD	4.5	4450	0	WITH 200 SX CMT
SURF	8.625	512		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2014 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING Phone: (620) 793-2315

Proposed Plugging Method: SET CIBP @ 4328' WITH 2 SX CMT. PLUG AT 1650' CIRCULATE TO SURFACE. POOH WITH TBG & REFILL CASING. TIED ONTO 8 5/8" X 4 1/2" ANNULUS & PRESSURE TO 300#.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 11/11/2014 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4325' WITH 2 SX CMT. 1ST PLUG AT 1670' WITH 100 SX CMT. CMT CIRCULATED TO SURFACE. POOH WITH TBG. TOP OFF WITH 16 SX CMT. PRESSURED UP 8 5/8" X 4 1/2" ANNULUS TO 300# WITH 4 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4388	4392		
4376	4382		

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

NOV 19 2014

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

12/4/14 cpm

SP