

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-147-01003-00-02  
Spot: SENENW Sec/Twnshp/Rge: 20-4S-18W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ELSIE-JACKSON OWWO Well #: 4  
County: PHILLIPS Total Vertical Depth: 3491 feet

Operator License No.: 5252  
Op Name: R. P. NIXON OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3415		150 sx
SURF	8.625	216		135 sx

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2014 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DUANE ACHTERBERG Company: R.P. NIXON OPERATIONS INC. Phone: (785) 656-0038

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
594' to surface w/200' on backside.  
Drilled cement from 720' - 1400'.  
Production perforations: 589' - 594'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/07/2014 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1396' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 412' and pumped 50 cement to circulate to surface. Pulled all tubing. Topped off 4 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 200 psi immediately.

GPS: 39.69521N -099.37150W

Perfs:

Top	Bot	Thru	Comments
590	594		
589	594		

Remarks:

Plugged through:

12/4/14 CPM

District: 04

Signed Pat Bedore  
(TECHNICIAN)

cc:uic

CM

KCC WICHITA

Form CP-2/3

NOV 21 2014

NOV 26 2014

RECEIVED