

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-30305-00-00
Spot: SESWSE Sec/Twnshp/Rge: 34-15S-14W
320 feet from S Section Line, 1652 feet from E Section Line
Lease Name: FIELD A Well #: 3
County: RUSSELL Total Vertical Depth: 3385 feet

Operator License No.: 31144
Op Name: REDDIG ENTERPRISES INC.
Address: 4325 177TH ST.
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3374		100 SX
SURF	8.625	282		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2014 1:00 PM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN REDDIG Company: REDDIG ENTERPRISES Phone: (785) 483-6170

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Bad casing in well.
Junk in hole at 2700'. Will plug from this depth.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 2700'. Plugged tubing. Could not pump into. Pulled tubing. Ran tubing to 2200' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 1700' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface w/70 sx cement and 150 # hulls. Pulled tubing. Tied to casing and topped off w/5 sx cement pressured to 400 psi. Tied to surface pipe and pumped 10 sx cement pressured up to 200 psi.

GPS: 38.69771 -098.80258

Perfs:

Top	Bot	Thru	Comments
3374	3385		

Remarks: QUALITY OILWELL CEMENTING TICKET # 876

Plugged through: DBL
CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

KCC WICHITA

NOV 26 2014

RECEIVED

12/4/14 CKM

CKM

Form CP-2/3

NOV 13 2014