

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-24013-00-00
Spot: SENEWSW Sec/Twnshp/Rge: 8-11S-11W
820 feet from S Section Line, 1005 feet from W Section Line
Lease Name: ZAMECNIK Well #: 1
County: RUSSELL Total Vertical Depth: 3950 feet

Operator License No.: 4787

Op Name: TDI

Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 sx

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/15/2014 12:00 AM

Plug Co. License No.: 33350

Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: LARRY

Company: SOUTHWIND DRILLING, INC.

Phone: (580) 430-8375

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER

WitnessType: NONE

Date/Time Plugging Completed: 11/15/2014 9:30 PM

KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @610 w/50 sx
2nd plug @420 w/100 sx
3rd plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: GLOBAL

Plugged through: DP

12/4/14 CKM

District: 04

Signed Ed Schumacher

(TECHNICIAN)

CM

KCC WICHITA

NOV 26 2014

RECEIVED

NOV 21 2014