

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20204-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 16-14S-10W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BAKER A Well #: 1
County: ELLSWORTH Total Vertical Depth: 2934 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2412		
PROD	5.5	2934		200 SX
SURF	8.625	254		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2014 12:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/20/2014 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG CIBP THAT HAD BEEN SET PREVIOUSLY. RUN TUBING TO 2381' AND PUMP 100 SXS CEMENT. PULL TUBING TO 1420' AND CIRCUALTE 150 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO 5.5" AND CIRCUALTE CEMENT UP SURFACE CASING. USED TOTAL OF 360 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
2462	2864	CSG	

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: PERF TECH #12349. QUALITY WELL CEMENT #697, 60/40 POZ, 4% GEL. WELL PLUGGED DUE TO 10 TA EXPIRATION.

Plugged through:

12/4/14 ccm

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK