

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-20216-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 19-14S-10W  
74 feet from S Section Line, 3589 feet from E Section Line  
Lease Name: COOK TWIN Well #: 6-A  
County: ELLSWORTH Total Vertical Depth: 2938 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2400		
PROD	5.5	2937		100 SX
SURF	8.625	275		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2014 12:30 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/19/2014 3:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG CIBP @ 2400'. PERFORATE AT 1200', 850', AND 325'. RUN TUBING TO 2370' AND PUMP 100 SXS CEMENT. PULL TUBING TO 1200' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. LET SET AWHILE AND CONNECTED ON TO 5.5" PUMPED ANOTHER 85 SX'S CIRCULATING CEMENT OUT OF SURFACE CASING. USED 345 SX'S CEMENT TOTAL.

Perfs:

Top	Bot	Thru	Comments
2872	2886	CSG	

Received  
KANSAS CORPORATION COMMISSION  
**DEC 01 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: PERF TECH #12234. QUALITY WELL #695. WELL PLUGGED DUE TO 10 YEAR TA EXPIRATION.

Plugged through: TBG

12/4/14 CFM

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

1/3K