

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-141-20387-00-00
Spot: S2N2S2S2 Sec/Twnshp/Rge: 10-9S-15W
900 feet from S Section Line, 2640 feet from E Section Line
Lease Name: BEISNER UNIT Well #: 1
County: OSBORNE Total Vertical Depth: 3572 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3570		140 SX
SURF	8.625	210		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2014 12:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: 11/12/2014- Ordered 350 sx 60/40 pozmix 4% gel cement, 10 sx gel and 300 # hulls.
11/13/2014- Ordered 300 sx 60/40 pozmix 4% gel cement 1/4 # flo-seal/sx and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2014 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

11/12/2014- Perforated at 195', 890', 1350' and 1625'. Ran tubing to 3240' and pumped 10 sx gel followed by 50 sx cement w/50 # hulls. Backside circulating. Pulled tubing to 1700' and pumped 100 sx cement. Pulled tubing to 700'. Started to pump and lost circulation. Pumped 75 sx cement and regained circulation. Continued pumping cement and lost circulation once again. Pumped a total of 150 sx cement w/200 # hulls at 700'. POOH. Shut down for the night.
11/13/2014- Ran tubing to 565' and floated the last 2 joints of tubing down. (18 joints in well). Pulled tubing to 500' (16 joints in well). Pumped 65 sx cement and circulated good cement out to the pit. POOH. Topped off w/5 sx cement and well stayed full. Braden head was dug out and found to be full of cement. (Library showed Allied Cementing ticket # 34572 w/PC at 1240' cemented w/650 sx cement and it circulated.)

GPS: 39.28020 -098.98291

Perfs:

Top	Bot	Thru	Comments
3309	3315		
3230	3234		
3006	3012		

Remarks: QUALITY CEMENTING TICKET # 720.721

Plugged through: TBG

12/4/14 CKM

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

KCC WICHITA

NOV 26 2014

RECEIVED

NOV 18 2014