

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20316-00-00
Spot: NESESE Sec/Twnshp/Rge: 23-14S-11W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: PRINC Well #: 1
County: RUSSELL Total Vertical Depth: 2885 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2885		225 SX
SURF	8.625	270		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2014 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL Phone: (785) 483-1821

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2014 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: _____ Perfs: _____

Perforated at 250', 750' and 1500'. Ran tubing to 2600' and pumped 100 sx cement. Both sides circulating fluids. Pulled tubing to 1150' and pumped 80 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 45 sx cement. Cement circulated out braden head. Shut in.

GPS: 38.81544 -098.50473

Remarks: ALLIED CEMENTING TICKET # 55567

Plugged through: TBG

12/4/14 CKM

District: 04

Signed Ray A Dinkel
KCC WICHITA (TECHNICIAN) CM

NOV 26 2014

RECEIVED

NOV 18 2014