

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-20370-00-00  
Spot: W2W2SW Sec/Twnshp/Rge: 24-14S-11W  
1320 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SEBESTA Well #: 7  
County: RUSSELL Total Vertical Depth: 2873 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2873		200 SX
SURF	8.625	268		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2014 9:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL Phone: (785) 483-1821

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2014 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforations: 250', 750' and 1500'. Ran tubing to 2600' and pumped 100 sx cement. Started to circulate fluid out both sides. Pulled tubing to 1150' and pumped 80 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 80 sx cement. Circulated cement out of the braden head. Shut in.  
GPS: 38.81631 -098.50096

Remarks: QUALITY CEMENTING TICKET # 693

Plugged through: TBG

12/4/14 *CKM*

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN) *CKM*

KCC WICHITA

NOV 26 2014

RECEIVED