

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23139-00-01
Spot: W2SEW Sec/Twnshp/Rge: 11-26S-4E
2970 feet from S Section Line, 3465 feet from E Section Line
Lease Name: ORBAN B Well #: 1
County: BUTLER Total Vertical Depth: 2730 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2325		
CIBP	5.5	2418		
PROD	5.5	2722		200 SX
SURF	8.625	256		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 08/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8/13/2014 SET CIBP @ 1954', DUMP BAILED 2 SXS CEMENT ON TOP. 8/21/2014, RIH W/TBG @ 1410', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 100 SXS CLASS A COMMON 3% CC 50# POLY FLAKE & DISPLACED IN CASING. LAYED DOWN TBG @ 310', REVERSED CIRCULATED HOLE CLEAN (310'-0'). WAITED 2 HOURS TAGGED CEMENT @ 1414'. RIH W/TBG @ 1320', CONSOLIDATED MIXED & PUMPED 130 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING, LAYED TBG DOWN @ 310', REVERSED CIRCULATED HOLE CLEAN (310'-0'). WAITED 2 HOURS. TAGGED CEMENT @ 367'. PRESSURED CASING @ 100#. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'-271' 4 - HOLES. SWEDGED INTO 5 1/2" CASING, CONSOLIDATED MIXED & PUMPED 95 SXS 60/40 POZ 4% GEL 25 CC. TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2424	2430	CSG	
2350	2353	CSG	
2070	2074	CSG	
1986	1988	CSG	
1970	1974	CSG	

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #46465.

Plugged through: TBG

12.4.14 CKM

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

✓