

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40457-00-00
Spot: SESWNWNW Sec/Twnshp/Rge: 32-25S-5E
4171 feet from S Section Line, 4659 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 5W
County: BUTLER Total Vertical Depth: 677 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	647		50 SX
SURF	7	88		50 SX

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 08/21/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 08/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 645', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED DOWN TBG @ 310', REERSED CIRCULATED HOLE CLEAN (310'-0'). WAITED 2 HRS TAGGED CEMENT @ 312'. PRESSURED CASING @ 300#, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'-271' 4 HOLES. SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL 2% CC. CEMENT CIRCUALTED TO QUICK. RIH W/TBG @ 290', CONSODLIATED MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. SWEDGED BACK INTO 4 1/2" CASING & PUMPED 10 SXS MORE. TOTAL 60 SXS. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
647	677	OH	

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #46466.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc: uic ✓

12/4/14 CKM