

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-23985-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 24-15S-15W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: SCHWIEN Well #: 1  
County: RUSSELL Total Vertical Depth: 3456 feet

Operator License No.: 32016  
Op Name: WELLS, RODGER D. DBA PIONEER RES  
Address: 80 WINDMILL DR.  
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2014 12:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.  
Proposal Revd. from: GEORGE Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 260 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 11/07/2014 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

1st plug @3344 w/50 sx  
2nd plug @930 w/50 sx  
3rd plug @500 w/80 sx  
4th plug @270 w/25 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED  
Plugged through: DP

12/4/14 ckm

District: 04 Signed Richard Williams (TECHNICIAN) CM  
KCC WICHITA  
NOV 26 2014  
RECEIVED  
NOV 21 2014  
Form CP-2/3