

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-009-22,388 0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address One Main Place, Suite 900, Wichita, Kansas 67202

Lease Name Neeland "A" Well No. 1

Location NE NE NW Sec. 8 Twp. 19 Rge. 12 ~~(East)~~ (West)

County Barton Total Depth 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. and Allied Cementing Co., Inc.

Address Box 823, Great Bend, Kansas License No. _____

Operation Completed: Hour: 5:00 PM Day: 6 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-211'-175 sacks common

Hole circulated and filled with mud. 50 sacks cement pumped through

drill pipe at 480'. 30 sacks cement pumped through drill pipe at 220'.

Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar

with 10 sacks cement. Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1981
6-12-81
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

FE 7-27-81

NV. NO. 6015-W