

15-009-30444-0000
Form CP-3
Rev. 6-26-62

KANSAS

JP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Jay-Bee Oil Company, Inc.

Complete Address: 511 Union Center, Wichita, Kansas

Lease Name Boor Well No. # 1

Location NW NE SW Sec. 23 Twp. 17 Rge. 15 (E) (W) X

County Barton Total Depth 3550

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company

Address: 500 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 3 PM Day 22 Month 8 Year 1966

The Above well was plugged as follows:

8 5/8" 279' Cwc.
Filled hole with heavy mud to 550', set plug, displaced 25 sax cement thru drill pipe.
Displaced mud to 270', set plug with 1/4 sax hulls, & displaced 20 sax cement thru
drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 15 sax cement with Sun
Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/66 *RCW*
INV. NO. 3810-4 *08-26-66*

Signed: *Don L. ...*
Well Plugging Supervisor