

KANSAS

Form CP-3
Rev. 6-26-62

15-185-13169-0000
RECEIVED
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

OCT -2 1967

10-02-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 9, 1967.

Operator's Full Name Morgenstern Oil Operations

Complete Address: P. O. Box 372, Wichita, Kansas 67201

Lease Name Tucker Well No. # 1

Location NE SE NE Sec. 26 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3819'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Company

Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 9:45AM Day 30th Month Sept. Year 1967

The Above well was plugged as follows:

294' of 8 5/8" surface pipe, cemented with 200 sacks. 3817' of 5 1/2" long string, cemented with 125 sacks. Open hole. Plug and sand to the top of the Kansas City at 3300', and cemented with 5 sacks, with cement from 3300' to 3260'. 450' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 250', bridge plug and rock bridge from 250' to 240'. 8 sacks of cement was mixed in a barrel, and put on plug at 240', through the dump bailer, and let set overnight.

Next day hole was bailed dry, and 17 sacks of cement was added to the plug, with cement from 240' to 165'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/2/67

INV. NO. 6426-W