

State of Kansas



15-009-30500-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1966  
08-25-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Company has this  
date requested permission to plug the following described well:

Mr. Richard G. Smith guarantees payment of the plugging fee.

Operator's full Name: Richard G. Smith

Complete Address: 602 Rule Bldg., Wichita, Kansas

Lease Name: E. Mater Well No. # 1

Location: SE SW NW Sec. 11 Twp. 17 Rge. 15 (E)(W) X

County Barton Total Depth 3500 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Duke Burt was instructed to plug the well as follows:

8 5/8" 986' Cwc.

Filled hole with heavy mud to 980', displaced 25 sax cement thru drill pipe.

Mud to 500', set plug with 1/4 sax hulls, displaced 20 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement,

cementing to base of cellar.

Very truly yours,

*John L. ...*  
Conservation Division Agent