

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-01039-00-03
Spot: SWSENW Sec/Twnshp/Rge: 31-19S-13W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: GRUNWALD Well #: 1
County: BARTON Total Vertical Depth: 3560 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3558		100 SX
SURF	8.625	350		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2014 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 300 # hulls and 15 sx gel.
Dug out braden head and surface pipe was full of cement.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 760'. Ran tubing to 3400' and pumped 15 sx gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing w/100 sx cement and 50 # hulls. Pulled tubing. Topped off casing w/50 sx cement.
11/03/2014- Topped off casing w/40 sx cement.

GPS: 38.35562 -098.80503

Perfs:

Top	Bot	Thru	Comments
3499	3502		
3482	3490		
3466	3474		
3246	3251		
3190	3196		

Remarks: ALLIED CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
11/25/14 CCM (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

NOV 04 2014

NOV 19 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3