

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-02752-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 32-8S-24W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: HOLLEY UNIT Well #: 10-5  
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 34402  
Op Name: GARAL, DONNA AND VINCENT INNON  
Address: 30-38 48 ST  
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4010		150 SX
SURF	8.625	203		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2014 2:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: JASON DINGES Company: WHITETAIL CRUDE, INC Phone: (785) 623-8060

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Shot perforations at 2120', 1245' and 195'.  
Bridge plug at 2584'. Can not drill through. Will have to plug well from this depth.  
Bottom perforations at 3674' - 3768' and 3889' - 3895'.  
Top of casing reported to be in bad condition. Had to shut down to get a welder to repair casing. Will continue job on 11/03/14.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2014 12:15 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 2550' and pumped 100 sx cement. Pulled tubing to 2500' and pumped 230 sx cement w/500 # hulls. Lost circulation. Let well set 30 minutes. Pumped 85 sx cement. Good circulation of cement. Pulled tubing out. Topped off w/20 sx cement. Casing and backside full.

GPS: 39.30678 -100.02708

**Perfs:**

Top	Bot	Thru	Comments
3889	3895		
3887	3891		
3764	3768		

Received  
KANSAS CORPORATION COMMISSION


**NOV 14 2014**

Remarks: GLOBAL CEMENT TICKET # 1474

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 04

Signed   
(TECHNICIAN)

11-25-14 CLKM

CM

NOV 8 6 2014

Form CP-2/3