

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-02978-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 15-7S-19W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: CLARENCE HOLSMAN Well #: 2
County: ROOKS Total Vertical Depth: 3408 feet

Operator License No.: 3077
Op Name: JOHNSON OIL, A GENERAL PARTNERS
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3407	0	200 SX
SURF	8.625	195	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2014 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN JOHNSON Company: SWIFT SERVICES, INC. Phone: (785) 543-6171

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/200 # hulls. Shot perforations in tubing at 1500' and 850'.
Perforations at 3310' - 3318', 3290' - 3298', 3334' - 3340'.
2 3/8" tubing cemented in hole to 2977'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to tubing and pumped 150 sx cement w/100 # hulls. Shut in 150 psi. Tied on to backside and squeezed w/5 sx cement. Shut in 150 psi.
GPS: 39.44018 -099.42020

Perfs:

Top	Bot	Thru	Comments
3334	3340		
3310	3318		
3290	3298		

Received
KANSAS CORPORATION COMMISSION


Remarks: SWIFT CEMENT TICKET # 26961

Plugged through: TBG

NOV 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed 
(TECHNICIAN)

11-25-14 CKM

CM

NOV 10 2014