

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22776-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 1-19S-11W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: KLEPPER Well #: 1
County: BARTON Total Vertical Depth: 3432 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3431		125 SX
SURF	8.625	282		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2014 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K & N PETROLEUM Phone: (620) 793-5838

Proposed
Plugging
Method:

Ordered 350' sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 540' and 260'. Ran tubing to 3317' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 80 sx cement w/250 # hulls. Pulled tubing to 540'. Circulated cement to surface w/80 sx cement on casing. Circulated cement to surface on surface pipe w/55 sx cement. Pulled tubing. Topped off w/10 sx cement.

GPS: 38.42103 -098.48259

Perfs:

Top	Bot	Thru	Comments
3380	3382		
3360	3364		
3172	3180		
3086	3090		
3056	3059		

Remarks: COPELAND ACID AND CEMENT

Plugged through: CSG

District: 04

Signed Bruce Rodie
11/25/14 CCM (TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

NOV 13 2014

NOV 19 2014

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS