

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22319-00-01
Spot: SWSNWSE Sec/Twnshp/Rge: 15-27S-13W
1531 feet from S Section Line, 1790 feet from E Section Line
Lease Name: PATTON-CARVER TRUST OW Well #: 1-15
County: PRATT Total Vertical Depth: 4191 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4224	0	WITH 175 SX CMT
SURF	13.375	267		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2014 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM LYMAN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed
Plugging
Method:

PLUG 30 SX CMT & 150# HULLS ON BOTTOM. PERFORATE AT 840' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/03/2014 10:45 AM

Witness Type: COMPLETE (100%)
KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET BOTTOM PLUG AT 3840' WITH 150# HULLS & 30 SX CMT. PERFORATE AT 860'. PUMPED DOWN 4 1/2" CASING WITH 260 SX CMT. CMT DID NOT CIRCULATE. PERFORATE AT 200'. PUMPED DOWN 4 1/2" CASING. COULD NOT PUMP INTO PERFS. PERFORATED AT 150'. PUMPED DOWN 4 1/2" CASING WITH 80 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3988	3995		
3826	3836		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENTING.

Plugged through: TBG

District: 01

Signed Robert Dickerson
11-25-14 ckm Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

RECEIVED
NOV 11 2014

KCC DODGE CITY

NOV 17 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3