

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22195-00-00  
Spot: NWSE Sec/Twnshp/Rge: 26-26S-11W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: MEZGER Well #: 1  
County: PRATT Total Vertical Depth: 4390 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4260		WITH 2 SX CMT
PROD	5.5	4389	1831	WITH 150 SX CMT
SURF	8.625	440		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2014 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP AT 4260' WITH 2 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 470' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 10/27/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4260' WITH 2 SX CMT. 1ST PLUG AT 712' WITH 10 SX GEL & 50 SX CMT.  
2ND PLUG AT 498' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4298	4302		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENT.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

11-25-14 CKM

Received  
KANSAS CORPORATION COMMISSION

NOV 17 2014

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED

OCT 29 2014

KCC DODGE CITY

Form CP-2/3