

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20061-00-00
Spot: S2SE Sec/Twnshp/Rge: 7-22S-40W
666 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HCU (WHEATLAND 1) Well #: 0720
County: HAMILTON Total Vertical Depth: 2745 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2669		
PROD	4.5	2745	0	WITH 700 SX CMT
SURF	8.625	243		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2669' WITH 30 SX CMT. PULL TO 1250' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2014 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2669'. PUMP 35 SX CMT FROM 2638' TO 2100'. CIRCULATE CMT FROM 1314' TO 0' WITH 80 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2719	2732		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
11-25-14 CEM (TECHNICIAN)

RECEIVED
NOV 11 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
NOV 17 2014
CONSERVATION DIVISION
WICHITA, KS

SP