

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23398-00-00
Spot: S2SENESE Sec/Twnshp/Rge: 29-14S-14W
1400 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHOENBERGER A Well #: 1
County: RUSSELL Total Vertical Depth: 3475 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3420	2206	200 SX
SURF	8.625	805		340 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JIM SCHOENBERGER Company: JASON OIL COMPANY, INC. Phone: (785) 483-4204

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and sand for the bottom.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2014 8:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

11/04/2014- Sanded off bottom to 2960' and 4 sx of cement on top. Cut casing.
11/05/14-Casing cut at 2206' and pulled to 1600'. Pumped 125 sx cement w/300 # hulls. Pulled casing to 820' and pumped 40 sx cement w/50 # hulls. Pulled casing to 350' and pumped 100 sx cement. Cement circulated. POOH. Cellar stayed full.
5 1/5" casing cut at 2206' leaving 1214' of casing in the hole. 51 joints of casing were recovered.
GPS: 38.80216 -098.89314

Perfs:

Top	Bot	Thru	Comments
3254	3256		
3154	3158		
3014	3018		

Remarks: QUALITY CEMENTING TICKET # 684

Plugged through: CSG

District: 04

Signed

Ray A Dinkel

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

11/25/14 ccm cm

NOV 13 2014

NOV 19 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3