

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-01796-00-00
Spot: SESWSWSW Sec/Twnshp/Rge: 9-12S-15W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SUTTON B Well #: 1
County: RUSSELL Total Vertical Depth: 3290 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3288		150 sx
SURF	8.625	277		175 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2013 12:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Revd. from: DAN WEINHOLD Company: GLM COMPANY Phone: (785) 483-1599

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement.
Perforations at 230'. Squeezed hole in casing and got out of pipe at 686' when drilling out cement. Left 5 1/2" RB plug in well at 2950'.
No CP-1

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2013 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 686' and pumped 75 sx cement. Cement circulated out backside. POOH.
Pumped 10 sx cement at 800 psi and shut in. Braden head was inside a 55 gallon barrel and full of cement. Will cut off and see what we have at surface at a later date.
11/04/2014- Ready-Mix top off between 8 5/8" and 5 1/2" casing w/1 yard of cement slurry and filled cellar.

GPS: 39.1707 -099.00068

Remarks: QUALITY CEMENTING TICKET # 7221

Plugged through: TBG

District: 04

Signed Ray A Dinkel
11-25-14 ckm (TECHNICIAN) cm

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

NOV 18 2014

NOV 19 2014

CONSERVATION DIVISION
WICHITA, KS