

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20351-00-01
Spot: SWSW Sec/Twnshp/Rge: 30-1S-41W
652 feet from S Section Line, 4658 feet from E Section Line
Lease Name: OCHSNER A Well #: 1
County: CHEYENNE Total Vertical Depth: 5529 feet

Operator License No.: 34734
Op Name: PETRO RIVER OPERATING, LLC
Address: 4925 GREENVILLE, STE 900
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5014		200 sx
SURF	8.625	262		170 sx

Well Type: SWD UIC Docket No: D30060.0 Date/Time to Plug: 11/05/2014 8:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DANIEL SMITH Company: PETRO-RIVER Phone: (903) 705-8900

Proposed Plugging Method: 8 5/8" surface casing set at 262' w/170 sx cement. 4 1/2" production casing set at 5014' w/200 sx cement. DV Tool set at 2220' w/125 sx cement. TOC 1400'. Perforations: 4761' - 4764'. Well converted to SWD. CIBP set at 3620'. 3 cement squeezes at 3196'. Perforations: 3416' - 3514'. The well failed an MIT on March 24, 2011. Well transferred from Metro Energy Group # 33638 to Petro River Operating LLC # 34734. Casing squeezes: 2999' - 3348', 3199' - 3230', 3199'. Casing leak at 668' - 700'. Squeezed leak with 170 sx. Cement to surface from 8 5/8" surface casing. Shut in and pressured. Casing remediation failed. Operator decided to plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2014 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Tagged top of cement at 2200'. Pulled tubing to 2180'. Pumped 75 sx cement w/300 # hulls. Pulled tubing to 1100' and pumped 100 sx cement w/300 # hulls. Cement to surface. Pulled tubing to surface. Topped off 4 1/2" casing w/10 sx cement. Casing full. 8 5/8" surface casing full of cement. Plug complete.

GPS: 38.93227 -101.97142

Perfs:

Top	Bot	Thru	Comments
4761	4765		

Received
KANSAS CORPORATION COMMISSION

NOV 14 2014

Remarks: EXCELL SERVICES INC. SERVICE RIG. ALLIED CEMENT SERVICES TICKET # 64.222

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

cc: UIC
11-25-14 CFM

CS

NOV 07 2014