

✱ Corrected ✱

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20089-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 17-15S-17W
 feet from Section Line, feet from Section Line
Lease Name: LEIKER C Well #: 2
County: ELLIS Total Vertical Depth: 3564 feet

Operator License No.: 5242
Op Name: PETROLEUM MANAGEMENT, INC.
Address: 14201 E CENTRAL
WICHITA, KS 67230

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|---------------|
| PROD | 4.5 | 3561 | 0 | w/200 sxs cmt |
| SURF | 8.625 | 1131 | 0 | w/450 sxs cmt |

Well Type: EOR UIC Docket No: E15655.1 Date/Time to Plug: 08/03/2006 4:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: GARY REED Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed Plugging Method: Ordered 200 sxs 60/40 poMix - 10% gel - 400# hulls.
Dakota 167'-467'. Anhy.1119'-1155'. Salt 1501'-1771'. SHOOT OFF CASING @ 1905'. PULL TO 1775' SPOT 80 SX PLUG; PULL TO 1175' SPOT 35 SX PLUG; PULL TO 150' CIRCULATE CEMENT TO SURFACE W/ 50 SX.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2006 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service sanded off bottom to 3285' and topped with 4 sxs cement.
Cut casing at 1905' - pulled to 1775'. Quality rigged to casing - pumped 80 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled casing to 1190' - pumped 35 sxs 60/40 pozmix with 100# hulls mixed in.
Pulled casing to 510' - pumped 35 sxs.
Pulled casing to 170' - pumped 40 sxs cement to circulate cement to surface.
Pulled casing and topped with 10 sxs.
Hole was standing full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3401 | 3405 | | |

Remarks: QUALITY CEMENTING

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

CC: UIC
CKM- 11.25.14
Pulled in 06 -
corrected copy
of CP-2/3

Received
KANSAS CORPORATION COMMISSION
NOV 19 2014
CONSERVATION DIVISION
WICHITA, KS

NOV 14 2014