

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21657-00-01
Spot: SESWSW Sec/Twnshp/Rge: 5-8S-23W
330 feet from S Section Line, 990 feet from W Section Line
Lease Name: MONTGOMERY Well #: 3
County: GRAHAM Total Vertical Depth: 3770 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3769		125 SX
SURF	8.625	168		145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2014 12:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: THOMAS ATKINS Company: MURFIN DRILLING CO., INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls,
DV Tool set at 1923'.
Perforations: 3546' - 3550', 3562' - 3565', 3583' - 3586', 3644' - 3650', 3666' - 3668', 3680' - 3682', 3702' - 3706'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2014 7:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3460' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2500' and pumped 135 sx cement. Good circulation of cement. Pulled tubing. Squeezed casing w/20 sx cement. Shut in pressure 350 psi. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 100 psi.

GPS: 39.37969 -099.91677

Perfs:

Top	Bot	Thru	Comments
3583	3586		
3562	3565		
3546	3550		

Received
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED CEMENT TICKET # 47727

NOV 14 2014

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Marvin Mills
11/25/14 CKM

(TECHNICIAN)

CM

NOV 06 2014