

15-009-22388-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC⁸ TWP. 19 RGE! 2 ~~XXX~~/W
 Location as in quarters or footage from lines:
NE NE NW

Lease Owner Raymond Oil Co., Inc.
 Lease Name NEELAND Well No. 1
 Office Address One Main Place, Suite 900, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed June 6, 1981
 Application for plugging filed 6-6-81
 Plugging commenced 6-6-81
 Plugging completed 6-6-81
 Reason for abandonment of well or producing formation

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~Duane Rankin~~ Gilbert Toman

Producing formation Depth to top bottom T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

Bottom Plug set at 540' w/50 sacks 50/50 Pozmix, 4% gel, 3%cc thru drill pipe
Middle Plug set at 220' w/30 sacks " " " " " thru drill pipe
Top plug at 40' w/10 sacks cement " " " " "
10 sacks cement in rat hole.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this form)
 Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF ~~XXX~~ KANSAS COUNTY OF BARTON, ss.
DARREL ANDERSON (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Darrel Anderson
Box 823-Great Bend, Ks. 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1981

Dorothy M. Haque
 Notary Public.

My Commission expires: 4-11-1982

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 009 — 22,388
County Number

Operator
Raymond Oil Company, Inc.

Address
One Main Place - Suite 900 - Wichita, KS 67202

Well No. 1 Lease Name Neeland "A"


Footage Location
330 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor Duke Drilling Co., Inc. Geologist Richard E. Rowland

Spud Date 5-31-81 Date Completed 6-6-81 Total Depth 3350 RTD P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

S. 8 T. 19S R. 12 ^{1/E}/_W
Loc. NE NE NW
County Barton



Elev.: Gr. 1814
DF 1818 KB 1820

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	20#	211'	Common	175	4% gel 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1981

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				CONSERVATION DIVISION Wichita, Kansas
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

AC: State Corp

Operator Raymond Oil Company, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Neeland "A"	Dry hole
S 8 T 19S R 12 / # W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1	3130	3200	SAMPLE LOG TOPS	
15-30-15-30 Rec. 10' mud FP 51-61 71-71 SIP 710 - 558			Anhydrite Elmont Topeka - Liebner Toronto Douglas Br Lm Lansing RTD	651 2661 3006 -- 2735 3024 3040 3113 3128 3350
Plugged 6-6-81				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	RAYMOND OIL COMPANY, INC. <i>Wm. M. Raymond</i> Wm. M. Raymond <small>Signature</small> President <small>Title</small> June 25, 1981 <small>Date</small>
---------------	--

DRILLERS WELL LOG

DATE COMMENCED: May 31, 1981
DATE COMPLETED: June 6, 1981

Raymond Oil Co., Inc.
NEELAND A #1
NE NE NW
Sec. 8-T19S-R12W
Barton County, Ks.

0 - 215' Surface Soil, Sand
215 - 651' Sand, Shale, Red Bed
651 - 681' Anhydrite
681 - 3006' Shale, Lime
3006 - 3024' Lime & Shale
3024 - 3040' Lime
3040 - 3113' Shale
3113 - 3126' Lime & Shale
3126 - 3350' Lime
3350' RTD

ELEVATION: 1820 K.B.

FORMATION DATA

ANHYDRITE 651'
HEEBNER 3006'
TORONTO 3024'
DOUGLAS 3040'
BROWN LIME 3113'
LANSING 3126'
BASE K.C. 3350'
R.T.D. 3350'

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1981

CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE: Set new 8-5/8" pipe, 20# w/175 sacks common, 4% Gel, 3%cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Darrel Anderson, of lawful age, does swear and state that the facts and figures herein contained are true and correct to the best of his knowledge.

Darrel Anderson

Subscribed and sworn to before me this 8TH day of June 1981

My Comm. Expires: 2-11-1982

Deborah M. Hague
Notary Public