

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County, Sec. 10 Twp. 17S Rge. XXV 15 (W)

Location as "NE/CNWxSWx" or footage from lines NE-NE-SE

Lease Owner Champlin Petroleum Company

Lease Name A. & F. Mater Well No. 1

Office Address P. O. Box 308, Ellinwood, Kansas, 67526

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 19 19 66

Application for plugging filed May 19 19 66

Application for plugging approved (Verbal) May 19 19 66


Plugging commenced May 19 19 66

Plugging completed May 19 19 66

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Don Turon, Russell, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3585 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	1002.42	None

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 3585' T. D. to 350'. Pushed 1/4 sack of hulls, then plug to mud at 350', and spotted 25 sacks of cement through drill pipe. Then filled hole with heavy mud to 40' and ran 1/2 sack of hulls and plug and 15 sacks of cement filling hole to bottom of cellar. Pumped 2 sacks of cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza, Wichita, Kansas, 67202

STATE OF KANSAS, COUNTY OF BARTON, ss.  
J. W. Meyers

(employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Meyers  
J. W. Meyers, District Superintendent  
P. O. Box 308, Ellinwood, Kansas, 67526  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May 1966

My commission expires 5-22-66.

N. Kenneth Stivers  
Notary Public.

CHAMPLIN PETROLEUM COMPANY

A. & F. MATER #1

NE NE SE 10-17S-15W  
Barton County, Kansas

0' - 45'	Surface Soil and Rock
45' - 541'	Shale and Shells
541' - 604'	Dakota Sand
604' - 1,001'	Red Bed and Shale
1,001' - 1,025'	Anhydrite
1,025' - 1,260'	Shale and Shells
1,260' - 1,724'	Salt and Shale
1,724' - 3,260'	Shale and Lime
3,260' - 3,432'	Lansing Lime
3,432' - 3,446'	Lime and Shale
3,446' - 3,448'	Lime
3,448' - 3,550'	Lime and Shale
3,550' - 3,572'	Conglomerate
3,572' - 3,585'	Arbuckle
3,585'	TOTAL DEPTH