

LEASE NAME Benedict Axman

WELL NUMBER 1

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 14 TWP. 17 RGE. 15 (E) or (W)

COUNTY Barton

Date Well Completed 04-27-66

Plugging Commenced 04-19-95

Plugging Completed 04-25-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St., Newton, Kansas 67114-8827

PHONE# (316) 283-0232 OPERATORS LICENSE NO. 30742

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-19-95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3510' Bottom 3517' T.C. 3517'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content Surface	From	To	Size	Put in	Pulled out
				8 5/8"	996'	0
	Production			5 1/2"	3510'	1930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Bottom Plug: sanded off to 3460'. 5 sks of cement. Allied mixed 120 sks of cement with hulls. Displaced it down to 1750'. Mixed 40 sks of cement and displaced it down to 1025'. Mixed 115 sks of cement displaced it down to 525'. Circulated cement to surface from 525'. Circulated full of cement

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 95

Karlynn K. Beck
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM

