

4-060979

15-009-30526 9000

10-3

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-1966

NE SW NW /4 SEC. 23, 17 S, 15 W
3638 feet from S section line
4290 feet from E section line

Operator license# 3911

Lease Mary Asman Well # 2

Operator: RAMA Operating, Co.

County: Barton 110.98

Address: P.O. Box 159
Stafford, Kansas 67578

Well total depth 3515 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 274 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: Box 209 - Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 3 Month: October Year: 1996

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 210 sxs 60/40 posmix - 10% gel - hulls.

Rec'd 10-21-96

KANSAS STATE CORPORATION COMMISSION
OCT 21 1996

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:15 P.M., Day: 3, Month: October, Year: 1996


Actual plugging report: 8 5/8" to 274' w/175 sxs. 4 1/2" to 3442' cwc with 130 sxs. Squeezed at 418' three times with total of 185 sxs. Perforated at 975' and 1675'. Tied onto annulus and pumped 5 sxs cement with instant pressure of 400#. Tied onto production casing and pumped 110 sxs cement with 300# hulls followed by 95 sxs with 200# hulls.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: 1937 GL

I did [] / did not [X] observe the plugging.

INVOICED


(agent)

DATE 10-21-96

Form CP-2/3

INV. NO. 46760