

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3646

Operator: Haven Energy Corp
Name & Address 7310 E. Kellogg
Wichita, Ks. 67207.

5-5-88
API NUMBER 15-009-30258-0000
SW , SEC. 11, T 17 S, R 15 W/
1650 feet from S section line
3630 feet from E section line

Lease Name Edward Mater Well # 1
County Barton 113.26
Well Total Depth 3485 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 968

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00AM Day: 5 Month: May Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone)

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 5 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 968' w/400 sks. 5 1/2" set at 3475' w/150 sks.

Top perf at 3266'. Plugged bottom w/sand and 5 sks cement to 3200'. Shot pipe one time
and recovered 2600'. Pumped in 8 5/8" 25 sks cement w/5 sks Hulls. in 100' sks cement w/850 Psi.

STATE CORPORATION COMMISSION

JUL 6 1988

07-06-88

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)

Gilbert G. Scheck

DATE 7-7-88

INV. NO. 21216

5-5-88