

6 061950

8-30 009-30347-0001 132
D-14,283

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW _____, SEC. 11 _____, T 17 _____, S, R 15 _____ W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3646

Lease Name Max Mater Well # 4
County Barton 122.36
Well Total Depth 3765 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1018

Operator: Haven Energy Corp
Name & Address: 7310 E Kellogg
Wichita, Ks. 67207 - 1695

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 1:30PM Day: 30 Month: August Year: 19 89

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 50 sks common 300 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____
Operations Completed: Hour: 3:00PM Day: 30 Month: August Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 1018' w/450 sks. 5 1/2" set at 3606' w/600 sks.

Open hole 159'. Plugged bottom w/sand and 5 sks cemen to 3550'. Shot pipe one time and re-covered 0'. Pumped in 5 1/2" 50 sks common followed w/150 sks cement followed w/5 sks hulls in 150 sks cemen w/1000 psi. Pumped in 8 5/8" 0 sks cement w/300 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1989
09-27-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: By Halliburton Ran line to 3000'.
(If additional description is necessary, use BACK of this form)

I (did / did not) observe this plugging.

INVOICED

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

DATE 9-29-89

INV. NO. 25970